


Sewer Pump Station No. 8 Improvements

Background	The City of Bowie's Sewer Pump Station No. 8 (PS No. 8) was originally constructed in 1980. This pump station contains three original pumps and is designed to convey approximately one third of total influent flow to the Bowie wastewater treatment plant. Due to the age, the pumps, piping and associated appurtenances are in critical need of replacement and upgrade.
Project Scope	The Scope of Work is to replace existing pumps, valves, piping and instrumentation and provide electrical and lighting improvements. To accomplish the needed work, the entire sewage pump station requires a shutdown. A temporary bypass system will be installed to pump the sewage to the treatment plant during the shutdown.
Project Manager	Name: Sam Kumar Phone: 240-508-5163 email: spaspunoori@cityofbowie.org
Total Project Cost	TBD
Design Consultant	RKK Consultants
Construction Contractor	TBD
Anticipated Construction Period	August 2021 – February 2022
Images / Attachments	
Last updated: 7/7/2021	